

# The Orchards at Orenco

A Model for Healthy, Durable, Low Energy Affordable Housing

Mike Steffen  
Walsh Construction Co.

WALSH Seminar  
June 2016



# Outline

- Background & Context
- Design
- Construction
- QA/QC / Commissioning
- Results
- The Building in Use
- Lessons Learned
  
- Orchards Phase II



# Learning Objectives

- Demonstrate how the Passive House standard has been applied successfully to affordable housing development, serving as a model for future developments in North America, and serving as a primary path to achieving net zero energy affordable housing
- Describe the key design measures incorporated in the overall building design, enclosure and mechanical systems to achieve Passive House certification
- Describe the integrated teamwork / process used by the project team in the design, construction and operation of high performance affordable housing
- Demonstrate how efficient design and cost optimization can be used to reduce the overall development and operating costs of affordable housing

# The Orchards at Orenco

- Affordable housing community in Hillsboro, OR
  - Phase I: 57 units of workforce housing  
(completed 6/2015)
  - Phase II: 58 units of workforce housing  
(completes 6/2016)
  - Phase III: 52 units of family/workforce housing (2018?)
- Developer/Owner:  
REACH Community Development


# REACH Community Development

- REACH's goal is to provide **Healthy, Safe and Affordable** living
- Affordability not only includes low rents but also close proximity to work and schools, and low **monthly utility bills**
- REACH set a goal in their 2010 Strategic Plan to have a Passive House project in their portfolio by 2015

# Why Passive House?

- Most rigorous building energy efficiency standard in world
- Achieve significant reductions of utility costs to residents, while improving comfort and durability
- The right path to net zero...

# Location








Image courtesy of Ankrom Moisan Architects

# The Orchards at Orenco



# Phase I Basics

- 57 units of affordable workforce housing
- 57,750 square feet
- 3-story, wood frame construction on concrete slab-on-grade foundation

# Project Team



**Owner/Developer**



**Owner's Representative**



**Architect of Record**



**General Contractor**



**Passive House Consultant**



**Design Architect**



**Mechanical Engineer**



**Structural Engineer**



**Civil Engineer**



**Landscape Architect**



**PHIUS+ Rater**



THE ORCHARDS

6520

# Design Overview

Photo Credit: Casey Braunger





# Aerial View from South

Image courtesy of Ankrom Moisan Architects





Image courtesy of Ankrom Moisan Architects

- Treated Floor Area**
- Tempered Area**


# First Floor Plan






# Passive House Doors (Interior)






### Typical Roof Assembly: R-81

- 80 mil TPO roof membrane (fully adhered, white)
- 1/2" coverboard
- 12" polyisocyanurate insulation
- Self-adhered rubberized asphalt membrane vapor barrier (serves also as temp. roof)
- 3/4" plywood
- Prefabricated wood truss framing (trusses @ 24"o.c.)
- 5/8" gypsum wall board (2 layers)



### Typical Exterior Wall Assembly: R-39

- Fiber cement siding w/ treated 1x wood furring @ 24" o.c.
- 1-1/2" rigid mineral wool insulation (8 lb. density)
- Spun-bonded polyolefin sheet water-resistive barrier
- 1/2" plywood with air sealing tape at all seams
- 2x10 wood framing (studs at 24" o.c.)
- 9 1/4" blown fiberglass insulation at all framing cavities
- Polyamide sheet vapor barrier
- 5/8" gypsum wall board



### Typical Slab Assembly: R-19

- 4" concrete slab
- 15 mil polymer sheet vapor barrier
- 4" Type II expanded polystyrene insulation
- Gravel base with radon mitigation system piping

# Enclosure Assemblies

Balconies

Eyebrows



Image courtesy of William Wilson Architects


# Shading Elements



# HVAC Design



# HVAC Design








**Mechanical Penthouse**

# HVAC Design



- 3 HRV Zones
- Cook ERV serves each zone



# HVAC Design

- Continuous 50cfm supply air per bedroom
- Continuous exhaust at kitchen and bath
- Electric cove heater in living room for user control & backup heat




Image courtesy of PAE Consulting Engineers

- Estimated at 20% of building heating load


- No active cooling at apartments

# Overheating?

- Exterior overhangs at all windows
- Solar blocking window screens for west facing units
- Residents need to open windows at night and close during the day...



# Water Heating



- Ultra high efficiency boiler with supplemental storage
- Insulated trunk supply lines with electric trace tape reheat

# Integrated Process

- Integrated team / collaborative approach
  - Owner + design team + construction team
- Design Charrette, leading to early concepts...

TRUSS

WALL


AB

ORWARDS @ OPENCE ——— EXT. WALL OPTIONS

2/29/12


WALL (A)

- 1 7/8" TJI WALL FRAMING
- 1 7/8" BLOWN FG INSUL.
- WWR-VALUE = R-39
- MOISTURE: FAIR




WALL (B)

- 2x10 WALL FRAMING
- 9 1/4" BLOWN FG INSUL.
- 1 1/4" MINERAL WOOL EXT. INSUL.
- WWR-VALUE = R-40
- MOISTURE: GOOD




WALL (C)

- 2x8 WALL FRAMING
- 7 1/4" BLOWN FG INSUL.
- 3" MINERAL WOOL EXT. INSUL.
- WWR-VALUE = R-40
- MOISTURE: BETTER




WALL (D)

- 2x6 WALL FRAMING
- 5 1/2" BLOWN FG INSUL.
- 5" MINERAL WOOL EXT. INSUL.
- WWR-VALUE = R-41
- MOISTURE: BEST!



WALL (E)

- 2x6 WALL FRAMING
- 5 1/2" BLOWN FG INSUL.
- 7 1/2" BLOWN FG INSUL. w/ 7 1/2" TJI TRUSS.
- WWR-VALUE = R-48
- MOISTURE: ?



# Integrated Process

- Integrated team / collaborative approach
  - Owner + design team + construction team
- Design Charrette, leading to early concepts...
- Highly iterative process
  - Design work → modeling work → cost analysis → constructability review
  - Repeat...



PHPP Schematic Design Results - CFC Application Iterations

3/14/2012



Iteration	#7 Thick Windows (New Window Schedule)		#8 Thick Wall (New Window Schedule)		UPDATED CLIMATE DATA, ENVELOPE, & FLOOR AREA, THERMAL MASS, APPLIANCE & LIGHTING CALCULATIONS	#9a CFC App Iterations Wall B,C,D + Cascadia + 80cfm		#9b CFC App Iterations Wall B,C,D + Cascadia + 60cfm		#9c CFC App Iterations Wall B,C,D + Zola + 80cfm		#10a CFC App Iterations Wall E + Cascadia + 80cfm		#10b CFC App Iterations Wall E + Cascadia + 60cfm		#10c CFC App Iterations Wall E + Zola + 60cfm	
	R-value	R-value	R-value	R-value		R-value	R-value	R-value	R-value	R-value	R-value	R-value	R-value	R-value	R-value	R-value	R-value
Walls	2x8 w/ Spray FG	28	2x6 w 5" Mineral Wool	43	Wall C: 2x8 + 3" Mineral Wool	42	Wall C: 2x8 + 3" Mineral Wool	42	Wall C: 2x8 + 3" Mineral Wool	42	Wall E: 2x6 + 9.5" TJI	61	Wall E: 2x6 + 9.5" TJI	61	Wall E: 2x6 + 9.5" TJI	61	
Window - typ size, apts	3x5 ft T/T & Fixed		3x5 ft T/T & Fixed		3x5 ft T/T & Fixed		3x5 ft T/T & Fixed		3x5 ft T/T & Fixed		3x5 ft T/T & Fixed		3x5 ft T/T & Fixed		3x5 ft T/T & Fixed		
Window - typ size, lobby	Ribbon of 3x5 ft T/T		Ribbon of 3x5 ft T/T		Ribbon of 3x5 ft T/T		Ribbon of 3x5 ft T/T		Ribbon of 3x5 ft T/T		Ribbon of 3x5 ft T/T		Ribbon of 3x5 ft T/T		Ribbon of 3x5 ft T/T		
Window - typ size, corridor end	(2) 3x5 ft		(2) 3x5 ft		(2) 3x5 ft		(2) 3x5 ft		(2) 3x5 ft		(2) 3x5 ft		(2) 3x5 ft		(2) 3x5 ft		
Window:Wall Ratio, average	18%		18%		18%		18%		18%		18%		18%		18%		
Window - frame, apts	uPVC T/T	6.0	Casc 300 T/T overinsulated	4.5	Casc 300 T/T overinsulated	4.5	Casc 300 T/T overinsulated	4.5	uPVC T/T overinsulated	6.0	Casc 300 T/T overinsulated	4.5	Casc 300 T/T overinsulated	4.5	uPVC T/T overinsulated	6.0	
Window - frame, lobby	uPVC T/T	6.0	Casc 400+300 overinsulated	4.2	Casc 300 T/T overinsulated	4.5	Casc 300 T/T overinsulated	4.5	uPVC T/T overinsulated	6.0	Casc 300 T/T overinsulated	4.5	Casc 300 T/T overinsulated	4.5	uPVC T/T overinsulated	6.0	
Window - glass south	EU IGU 0.5/0.5	11.4	LoE 180/180 Argon	7.5	LoE 180/180 Argon	7.5	LoE 180/180 Argon	7.5	EU IGU 0.5/0.5	11.4	LoE 180/180 Argon	7.5	LoE 180/180 Argon	7.5	EU IGU 0.5/0.5	11.4	
Window - glass north	EU IGU 0.5/0.5	11.4	LoE 366/180 Argon	8.2	LoE 180/180 Argon	7.5	LoE 180/180 Argon	7.5	EU IGU 0.5/0.5	11.4	LoE 180/180 Argon	7.5	LoE 180/180 Argon	7.5	EU IGU 0.5/0.5	11.4	
Window - glass east	EU IGU 0.5 solar control	11.4	LoE 366/180 Argon	8.2	LoE 366/180 Argon	8.2	LoE 366/180 Argon	8.2	EU IGU 0.5 solar control	11.4	LoE 366/180 Argon	8.2	LoE 366/180 Argon	8.2	EU IGU 0.5 solar control	11.4	
Window - glass west	EU IGU 0.5 solar control	11.4	LoE 366/180 Argon	8.2	LoE 366/180 Argon	8.2	LoE 366/180 Argon	8.2	EU IGU 0.5 solar control	11.4	LoE 366/180 Argon	8.2	LoE 366/180 Argon	8.2	EU IGU 0.5 solar control	11.4	
Doors - frame	uPVC T/T Door	5.9	Casc 301 T/T Door overinsul	4.7	Casc 301 T/T Door overinsul	4.7	Casc 301 T/T Door overinsul	4.7	uPVC T/T Door overinsulated	5.9	Casc 301 T/T Door overinsul	4.7	Casc 301 T/T Door overinsul	4.7	uPVC T/T Door overinsulated	5.9	
Roof	10" EPS over Sheathing	49	10" EPS over Sheathing	49	10" EPS over Sheathing	49	10" EPS over Sheathing	49	10" EPS over Sheathing	49	10" EPS over Sheathing	49	10" EPS over Sheathing	49	10" EPS over Sheathing	49	
Slab-field	Slab w 4" EPS	19	Slab w 4" EPS	19	Slab w 4" EPS	19	Slab w 4" EPS	19	Slab w 4" EPS	19	Slab w 4" EPS	19	Slab w 4" EPS	19	Slab w 4" EPS	19	
Slab-footer	Slab w 2" EPS	10	Slab w 2" EPS	10	Slab w 2" EPS	10	Slab w 2" EPS	10	Slab w 2" EPS	10	Slab w 2" EPS	10	Slab w 2" EPS	10	Slab w 2" EPS	10	
Slab-edge	Slab w 6" EPS	29	Slab w 6" EPS	29	Slab w 6" EPS	29	Slab w 6" EPS	29	Slab w 6" EPS	29	Slab w 6" EPS	29	Slab w 6" EPS	29	Slab w 6" EPS	29	
Thermal Mass	Dbl Drywall Walls & Ceilings Gypcrete fir w/o carpet		Dbl Drywall Walls & Ceilings Gypcrete fir w/o carpet		Dbl 5/8" Drywall Walls & Ceilings 1 1/2" Gypcrete fir w/o carpet		Dbl 5/8" Drywall Walls & Ceilings 1 1/2" Gypcrete fir w/o carpet		Dbl 5/8" Drywall Walls & Ceilings 1 1/2" Gypcrete fir w/o carpet		Dbl 5/8" Drywall Walls & Ceilings 1 1/2" Gypcrete fir w/o carpet		Dbl 5/8" Drywall Walls & Ceilings 1 1/2" Gypcrete fir w/o carpet		Dbl 5/8" Drywall Walls & Ceilings 1 1/2" Gypcrete fir w/o carpet		
Ventilation Rate (ACH)	0.32		0.32		0.87 ACH	0.85 ACH	0.85 ACH	0.85 ACH	0.87 ACH	0.85 ACH	0.85 ACH	0.85 ACH	0.85 ACH	0.85 ACH	0.85 ACH	0.85 ACH	
Ventilation Rate (cfm per apt)					80 cfm/apt	60 cfm/apt	60 cfm/apt	60 cfm/apt	80 cfm/apt	60 cfm/apt	60 cfm/apt	60 cfm/apt	60 cfm/apt	60 cfm/apt	60 cfm/apt	60 cfm/apt	
HRV recovery efficiency	88% (Zehnder HRVs)		83% (Ultimate Air ERV)		83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	83% (Ultimate Air ERV)	
HRV electrical efficiency (W/cfm)	0.75		0.75		0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	0.75 W/cfm	
Space Heating					80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	80% Heat Pump, COP = 4.2	
Water Heating					20% Direct Electric	20% Direct Electric	20% Direct Electric	20% Direct Electric	20% Direct Electric	20% Direct Electric	20% Direct Electric	20% Direct Electric	20% Direct Electric	20% Direct Electric	20% Direct Electric	20% Direct Electric	
Gas Boiler, 93% eff.					Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	Gas Boiler, 93% eff.	
Tank loss 250 BTU/hr					Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	Tank loss 250 BTU/hr	
Other	SPF in Plumbing Stack		SPF in Plumbing Stack		Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	Plumbing/Downspout Stacks:	
Heat Demand, Annual (kBtu/sf)	3.83		3.82		(8) 2x12, 24" stud bays filled with SPF 5.51 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 4.88 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 4.08 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 4.92 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 4.30 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 3.52 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 3.83 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 3.82 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 3.82 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 3.82 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 3.82 kBtu/sf.yr	(8) 2x12, 24" stud bays filled with SPF 3.82 kBtu/sf.yr	
Passivhaus Limit = 4.75																	
Recommend at this Stage = 3.8																	
Heat Load, Whole Bldg (BTU/hr)	104395		103183		112789 BTU/hr	105356 BTU/hr	95652 BTU/hr	105549 BTU/hr	98117 BTU/hr	89412 BTU/hr	104395 BTU/hr	103183 BTU/hr	103183 BTU/hr	103183 BTU/hr	103183 BTU/hr	103183 BTU/hr	
% Htg Deliverable w/ Ventilation Air	116%		121%		287%	230%	254%	307%	247%	275%	116%	116%	116%	116%	116%	116%	
Cooling Strategy	HRV w/o heat recovery Windows open night only		HRV w/o heat recovery Windows open night only		HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	HRV w/o heat recovery Windows open night only	
Frequency of Overheating (>77°F)	0.0%		0.0%		0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	
Recommend 0% for whole bldg																	
Primary Energy, Annual* (kWh/sf.yr)	11.1 kWh/sf.yr		10.3 kWh/sf.yr		11.1 kWh/sf.yr	10.3 kWh/sf.yr	10.1 kWh/sf.yr	10.9 kWh/sf.yr	10.1 kWh/sf.yr	9.9 kWh/sf.yr	11.1 kWh/sf.yr	10.3 kWh/sf.yr	10.3 kWh/sf.yr	10.3 kWh/sf.yr	10.3 kWh/sf.yr	10.3 kWh/sf.yr	
With Solar Thermal Collectors																	
Passivhaus Limit = 11.1																	
Recommend at this Stage = 8.9																	
* Data assumes PHPP default values for lighting, appliance and plug loads. Actual anticipated loads are over twice these values and will not meet the Primary Energy standard.												Annual Heat Demand with 12" Polysty Roof. 4.47 kBtu/sf.yr		Annual Heat Demand with 12" Polysty Roof. 3.86 kBtu/sf.yr			

Image courtesy of Green Hammer

Iteration Item	#7 Thick Windows (New Window Schedule)		#8 Thick Wall (New Window Schedule)	
		R-value		R-value
Walls	2x8 w/ Spray FG	28	2x8 w 5" Mineral Wool	43
Window - typ size, apts	3x5 ft T/T & Fixed		3x5 ft T/T & Fixed	
Window - typ size, lobby	Ribbon of 3x5 ft T/T		Ribbon of 3x5 ft T/T	
Window - typ size, corridor end	(2) 3x5 ft		(2) 3x5 ft	
Window:Wall Ratio, average	18%		18%	
Window - frame, apts	uPVC T/T	6.0	Casc 300 T/T overinsulated	4.5
Window - frame, lobby	uPVC T/T	6.0	Casc 400+300 overinsulated	4.2
Window - glass south	EU IGU 0.5/0.5	11.4	LoE 180/180 Argon	7.5
Window - glass north	EU IGU 0.5/0.5	11.4	LoE 366/180 Argon	8.2
Window - glass east	EU IGU 0.5 solar control	11.4	LoE 366/180 Argon	8.2
Window - glass west	EU IGU 0.5 solar control	11.4	LoE 366/180 Argon	8.2
Doors - frame	uPVC T/T Door	5.9	Casc 301 T/T Door overinsul	4.7
Roof	10" EPS over Sheathing	49	10" EPS over Sheathing	49
Slab-field	Slab w 4" EPS	19	Slab w 4" EPS	19
Slab-footer	Slab w 2" EPS	10	Slab w 2" EPS	10
Slab-edge	Slab w 6" EPS	29	Slab w 6" EPS	29
Thermal Mass	Dbl Drywall Walls & Ceilings Gypcrete fir w/o carpet		Dbl Drywall Walls & Ceilings Gypcrete fir w/o carpet	
Ventilation Rate (ACH)	0.32		0.32	
Ventilation Rate (cfm per apt)				
HRV recovery efficiency	88% (Zehnder HRVs)		83% (Ultimate Air ERV)	
HRV electrical efficiency (W/cfm)	0.75		0.75	

# Passive House Energy Analysis Summary

Euroline Scenario (50% CD Set)

12/24/2013



1323 SE 6th Avenue, Portland, OR, 503-804-1746

**Holiday Edition!**

RESULTS:			
Space Heating EUI:	4.24 kBTU/sf.yr	Total Source Energy EUI:	34.4 kBTU/sf.yr
Passive House Standard:	4.75 kBTU/sf.yr	Passive House Standard:	38.0 kBTU/sf.yr
Percent of Limit:	89%	Percent of Limit:	91%

ASSUMPTIONS:			
<b>Envelope:</b>		R-value	
<b>Walls:</b>	2x10 + 1.5" mineral wool advanced framed, 15% framing factor solid blocking @ exterior structural supports	39	
<b>Windows:</b>	EuroLine T/T uPVC overinsulated	7.2	R-frame
Glazing N/S:	LoE 180/180 Ar, SHGC=0.54	7.5	
Glazing E/W:	LoE 366/180 Ar, SHGC=0.24	8.2	
<b>Residential Doors:</b>	Euroline T/T Door uPVC overinsul. ADA sill (assumed 4600 Series)	4.3	R-frame
Glazing:	same as above		
<b>Commercial Doors:</b>	TBD Wood Fire-Rated Door	4.5	R-frame
Glazing:	LoE 366/180 Ar, SHGC=0.24	8.2	
<b>Roof:</b>	12" Polyiso over Sheathing	81	
<b>Slab:</b>	Field: 4" EPS II	19	
Interior Footings:	1" EPS IX	6	
Perimeter Footings:	4" EPS IX	20	
Vertical Perimeter:	4" EPS II	19	
<b>Airtightness:</b>	0.60 ACH @ 50 Pa		
<b>Other:</b>	Thermal Mass: Standard drywall 1 inch gypcrete floor topping w/o carpet Carpet in bedrooms only		
Cold Stacks:	Downspouts, Plumbing, Radon vents aggregated in: (8) 2x12, 24" stud bays filled with Dense-pack Cellulose		
<b>Heating System:</b>	80% Heat Pump, COP = 4.15 (average all systems) delivered via HRV supply & indoor heads 20% Electric-Resistance (in apartments) window watcher shut-off		
<b>Ventilation System:</b>	Ultimate Air ERV, 83% eff, 0.75 W/cfm Apartment Ventilation: 50 cfm/apt Comm. Rm. Ventilation: 0.06 cfm/sf baseline CO2 sensor steps to code max req't Circulation Ventilation: 0.06 cfm/sf Whole-Building Ave: 0.58 ACH Duct Insulation, HRV to Exterior: 4" FG w/ vapor barrier Fitness/Trash Exhaust: 900 cfm direct exhaust make-up air inlet provided from exterior to exhausted space		
<b>DHW System:</b>	Central Gas Heater w/ Trace Htg on Lines Water Heater efficiency = 94% Hot Water Line Insulation: (11) hot water riser lines as min. 3/4" continuous Low-flow fixtures throughout		
<b>Appliances:</b>	Refrigerator/Freezers: 370 kWh/yr ES rating or better Dishwashers: 275 kWh/yr ES rating or better Clotheswashers: 184 kWh/yr ES rating or better Clothesdryers: gas (moisture sensing recommended) Range/Oven: electric (convection recommended) Range Hood: recirculating; charcoal filter Elevator: 1800 kWh/yr i.e. Kone Ecospace, MRL Traction		
<b>Lighting:</b>	Residential: 100% fluorescent/LED Non-residential: 0.8 W/sf occupied areas 0.4 W/sf storage/circulation areas occupancy sensing all non-residential areas		
<b>Cooling Strategy:</b>	Windows open night only, closed during day "Hold-opens" recommended for windows' Turn position HRV supply air tempered by heat pump; supply temp ~50F HRV heat recovery bypass automated by thermostat		

Image courtesy of Green Hammer

# Integrated Process

- Integrated team / collaborative approach
  - Owner + design team + construction team
- Design Charrette, leading to early concepts...
- Highly iterative process
  - Design work → modeling work → cost analysis → constructability review
  - Repeat...
- Coordinating the work...













Tyvek  
COMMERCIALWRAP

COMMERCIALWRAP

PONT

Tyvek  
COMMERCIALWRAP

PONT

Tyvek  
COMMERCIALWRAP

Tyvek  
COMMERCIALWRAP

288383 0  
68270

Seattle  
100  
2012

Tyvek  
COMMERCIALWRAP

Tyvek  
COMMERCIALWRAP

Tyvek  
COMMERCIALWRAP







Stivac center  
3 on center



Call 1-800-44-TYVEK WWW.CONSTRUCTION.TYVEK.COM

**CH PONT** The miracles of science

**SIALWRAP**

**tyvek**

**SIALWRAP**

Call  
WWW.CONSTRUCTION.TYVEK.COM  
The miracles of science

Stivac center  
3 on center

Call 1-800-44-TYVEK WWW.CONSTRUCTION.TYVEK.COM  
**CH PONT** The miracles of science

**tyvek**  
SIALWRAP

**tyvek**  
SIALWRAP




















# The Importance of Details


- Success is achieved - or not - at the details!
- To ensure performance at the detail level, establish continuity of the **critical barriers** and then clearly indicate that continuity in the design drawings
  - **Water-shedding surface**
  - **Water-resistive barrier**
  - **Air barrier**
  - **Thermal barrier**
  - **Vapor barrier**

# Tracing The Critical Barriers


- Design and construction team members can use a review exercise where one traces the barriers through the various building enclosure drawings
- Verify continuity OR identify discontinuities in critical barriers
- Air barrier continuity is “proven” at the detail level; however, it is very helpful to construction team to indicate ABS in larger scale drawings



**3** ENLARGED ELEVATION AT UNIT TYP  
 A3.22 | 1/2" = 1'-0"



**4** WALL SECTION AT UNIT TYP.  
 A3.22 | 1/2" = 1'-0"



Images courtesy of Ankrom Moisan Architects

# Wall Section







Image courtesy of Ankrom Moisan Architects

## Design Drawing at Typical Exterior Wall to Foundation




**Coordination Drawing at Typical Exterior Wall to Foundation**































Image courtesy of Ankrom Moisan Architects

## Design Drawing at Typical Exterior Wall to Roof





**Coordination Drawing at Typical Exterior Wall to Roof**





















Protecto Wrap  
Premium Building Products  
That Protect  
J.S.-160H MAST  
S.P.S. Rubber Modified

EMFECN  
SUTON 112  
LTT19  
EF-102  
LEE S. WOODS  
INTERIOR CONSTRUCTION

Protecto Wrap

112



**tyvek**

CO

**TYVEK**

**COMMERCIALWRAP**

WWW.CONSTRUCTION.TYVEK.COM

The miracles of science™

Call 1-800-44-TYVEK WWW.CONSTRUCTION.TYVEK.COM

**DUPONT** The miracles of science™







**Tyvek**  
HOUSEWRAP

**Tyvek**  
science™

Report 838-2376 (R18)  
Call 1-800-352-2376  
www.tyvek.com





NE

100% Recycled  
Kwik  
100% Recycled  
100% Recycled  
100% Recycled









Tyvek  
COMMERCIALWRAP

Tyvek  
COMMERCIALWRAP

Tyvek  
COMMERCIALWRAP

Tyvek  
COMMERCIALWRAP




















0002 □ (02) □ (03) □ (04) □ (05) □ (06)















REST  
REHAU

1110206 - J44 35931-36TUW47G1 275  
2025-04-01 10:21:00 1990/13 481  
E-TEST Standard C.2.1  
No. 782 282005

meets the ASTM E1677 Type I Air Barrier requirements when installed as an air barrier according to DuPont™ Tyvek™ installation instructions (ICC-ES AC-308 pour les membranes Barrier & Air Barrier Material requirements. ICC-ES Evaluation Report E-1110-10-01-01)  
conformément aux exigences de la norme ASTM E1677 pour les pare-air de type I lorsqu'ils sont installés conformément aux instructions d'installation de DuPont™ Tyvek™ (Rapport d'évaluation ICC-ES AC-308 pour les membranes résistantes à l'eau et les pare-air. Rapport d'évaluation ICC-ES E-1110-10-01-01)







18"  
MIA to  
Bottom



























**Mechanical Penthouse**





Protecto Wrap  
 Tyvek  
 1-800-44-TYVEK  
 WWW.CONSTRUCTIONTYVEK.COM  
 The miracles of science

**TYVEK**  
**COMMERCIALWRAP**


Call 1-800-44-TYVEK WWW.CONSTRUCTIONTYVEK.COM  
**DU PONT** The miracles of science

**COMMERCIAL**

Call all 1-800-44-TYVEK WWW.CONSTRUCTIONTYVEK.COM  
**DU PONT** The miracles of science

Call 1-800-44-TYVEK  
**DU PONT** The miracles of science

**COMMERCIAL**



When installed as an air barrier according to ICC-ES E-1109, Tyvek Commercial Wrap meets the requirements of ICC-ES E-1109. Tyvek Commercial Wrap is also approved for use as a vapor barrier. Tyvek Commercial Wrap is also approved for use as a vapor barrier. Tyvek Commercial Wrap is also approved for use as a vapor barrier.





**Tyvek**  
COMMERCIALWRAP

**Tyvek**  
COMMERCIALWRAP

**Tyvek**  
COMMERCIALWRAP

**Tyvek**  
COMMERCIALWRAP

**Tyvek**  
COMMERCIALWRAP

**COMMERCIALWRAP**

**COMMERCIALWRAP**

**COMMERCIALWRAP**

**Tyvek**  
COMMERCIALWRAP

**Tyvek**  
COMMERCIALWRAP

**COMMERCIALWRAP**

**DU PONT**

**TYVEK**

**COMMERCIALWRAP**

Call 1-800-44-TYVEK [WWW.COMMERCIALWRAP.COM](http://WWW.COMMERCIALWRAP.COM)

**DU PONT** The miracle of science





**DUPONT**  
**Tyvek**  
COMMERCIALWRAP

**DUPONT**  
**Tyvek**  
COMMERCIALWRAP

**DUPONT**  
**Tyvek**  
COMMERCIALWRAP

**DUPONT**

**DUPONT**  
**Tyvek**  
COMMERCIALWRAP

**DUPONT**

Call 1-800-44-TYVEK  
**DUPONT**

Call 1-800-44-TYVEK  
**DUPONT**

Call 1-800-44-TYVEK  
**DUPONT** The miracles of science





DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP

DUPONT Tyvek COMMERCIAL WRAP





Tyvek  
COMMERCIAL WRAP

Tyvek  
COMMERCIAL WRAP

Tyvek  
COMMERCIAL WRAP

Tyvek  
COMMERCIAL WRAP

Tyvek  
COMMERCIAL WRAP

Tyvek  
COMMERCIAL WRAP

Tyvek  
COMMERCIAL WRAP

Tyvek  
COMMERCIAL WRAP

Honey Bucket

S-65

2638

2638



Photo Credit: Bygghouse













rek

Tyvek

Tyvek Tyvek

Tyvek Tyvek Tyvek Tyvek

EASB















# QA/QC / Commissioning

- Execution of the Work...
  - Qualified subcontractors with skilled/trained tradespeople
  - Self-performed work
- Contractor quality control
  - Superintendent / Project Engineer / QC Specialist
  - Enclosure Superintendent / Quality Director
- Commissioning (independent inspection and testing)
  - QED: Water testing at windows and doors
  - Earth Advantage (PHIUS+ Rater): Insulation, HVAC / Ductwork, Airtightness









CertainTeed

MEMBRAN

CertainTeed







Panera  
BREAD

Upper  
Cab.

CertainTeed

**MEMBRAIN**  
The SMART Vapor Retarder

CertainTeed





Unit 318  
BR Wall

Box = 10.3 oz

Box + insulation = 1 lb 2.9 oz

insulation = 1 lb 2.6 oz = 1.163 lb / ff<sup>2</sup>

unit 314  
BR Wall

1.388 lb

Box = 10.3 oz

Box + Insul = 1 lb 15.4 oz

Insul = 1 lb 5.1 oz = 1.32 lbs / ff<sup>2</sup>

Unit 314  
BR

Box = 2 lb 2.5 oz

1 lb 8.1 oz

1.5 lbs / ff<sup>2</sup>

**BOISE**



MANY NEEDS. ONE PAPER. PROVEN RESULTS.™

Formulated for Premium Performance  
in Printers, Copiers and Fax Machines.

20lb.  
75gsm | 10M

8.5x11  
216 x 279mm



Heavy Lift logo is a trademark of  
Boise Paper Holdings, L.L.C.,  
or its affiliates.

SUSTAINABLE FORESTRY INITIATIVE  
Certified Sourcing  
www.sfiprogram.org  
SFI-01168

**OX9001**  
Acid-Free | Libre de Acido | Sans Acide  
Multipurpose Paper / Multiple De Uso Papel /  
Papier A Tous Usages  
Made in U.S.A. / Hecho en U.S.A. / Fabriqué aux E.-U.  
Boise Paper Holdings, L.L.C., P.O. Box 990050, Boise, ID 83790







Iyvek

Iyvek

Iyvek

LGAS







Do Not Enter  
Door Closed for Air  
Testing

1201M  
2x4  
2x6  
2x8  
2x10  
2x12  
2x14  
2x16  
2x18  
2x20  
2x22  
2x24  
2x26  
2x28  
2x30  
2x32  
2x34  
2x36  
2x38  
2x40  
2x42  
2x44  
2x46  
2x48  
2x50  
2x52  
2x54  
2x56  
2x58  
2x60  
2x62  
2x64  
2x66  
2x68  
2x70  
2x72  
2x74  
2x76  
2x78  
2x80  
2x82  
2x84  
2x86  
2x88  
2x90  
2x92  
2x94  
2x96  
2x98  
2x100

°F

52.0



43.6

 **FLIR**





14-11488  
14-11488.F01  
PH2

14-11488  
14-11488.F01  
PH2

14-11488  
14-11488.F01  
PH2

14-11488  
14-11488.F01  
PH2









**Preliminary Airtightness Test Result: 0.0875 ACH<sub>50</sub>**

EXIT







**Final Airtightness Test Result: 0.133 ACH<sub>50</sub>**



Passive House Institute US

CERTIFICATION

The Passive House Institute US Awards



The Designation of

**PHIUS+ CERTIFIED PASSIVE HOUSE**

PROJECT NAME: **Orchards at Orenco** 6250 NE Cherry Drive, Hillsboro, OR 97124

PROJECT OWNER: **REACH Community Development**

CPHC: **Dylan Lamar**

DATE: **June 12, 2015**

Executive Director

• TREATED FLOOR AREA	42,584	ft <sup>2</sup>
• ANNUAL HEAT DEMAND	5.94	kBTU/(ft <sup>2</sup> ·yr)
• ANNUAL COOLING DEMAND	0.13	kBTU/(ft <sup>2</sup> ·yr)
• SPECIFIC PRIMARY ENERGY DEMAND	35.1	kBTU/(ft <sup>2</sup> ·yr)
• PRESSURIZATION TEST RESULTS	0.13	ACH <sub>50</sub>
• HEATING LOAD	2.37	BTU/(ft <sup>2</sup> ·hr)
• COOLING LOAD	2.20	BTU/(ft <sup>2</sup> ·hr)





Passive House Institute US

CERTIFICATION

The Passive House Institute US Awards



The Designation of

**PHIUS+ CERTIFIED PASSIVE HOUSE**

PROJECT NAME: **Orchards at Orenco** 6250 NE Cherry Drive, Hillsboro, OR 97124

PROJECT OWNER: **REACH Community Development**

CPHC: **Dylan Lamar**

DATE: **June 12, 2015**

Executive Director

• TREATED FLOOR AREA	42,584	ft <sup>2</sup>
• ANNUAL HEAT DEMAND	5.94	kBTU/(ft <sup>2</sup> ·yr)
• ANNUAL COOLING DEMAND	0.13	kBTU/(ft <sup>2</sup> ·yr)
• SPECIFIC PRIMARY ENERGY DEMAND	35.1	kBTU/(ft <sup>2</sup> ·yr)
• PRESSURIZATION TEST RESULTS	0.13	ACH <sub>50</sub>
• HEATING LOAD	2.37	BTU/(ft <sup>2</sup> ·hr)
• COOLING LOAD	2.20	BTU/(ft <sup>2</sup> ·hr)



# Results

- Airtightness: 0.13 ACH<sub>50</sub>
- Annual Heat Demand: 5.94 kBTU/sf/yr
- Annual Cooling Demand: 0.13 kBTU/sf/yr
- Specific Primary Energy Demand: 35.1 kBTU/sf/yr
- Heating Load: 2.37 BTU/sf/hr
- Cooling Load: 2.20 BTU/sf/hr
- Total Site EUI (incl. anticipated plug loads): 22.5 kBTU/sf/yr



# Results

- Airtightness: 0.13 ACH<sub>50</sub>
- Annual Heat Demand: 5.94 kBTU/sf/yr
- Annual Cooling Demand: 0.13 kBTU/sf/yr
- Specific Primary Energy Demand: 35.1 kBTU/sf/yr
- Heating Load: 2.37 BTU/sf/hr
- Cooling Load: 2.20 BTU/sf/hr
- Total Site EUI (incl. anticipated plug loads): 22.5 kBTU/sf/yr
  
- REACH is tracking energy usage (whole building and unit-by-unit) and will report data...



Photo Credit: Casey Braunger





Photo Credit: Casey Braunger





Photo Credit: Casey Braunger






Photo Credit: Casey Braunger



12  
Welcome to The Orchards  
at Orengo  
• Don't forget the Grand opening on June 29th at 10:30 a.m.



The Building in Use


Photo Credit: Casey Braunger



# Energy Monitoring




## The Orchards



Have a great day and stay warm!

- Turn your heat down at night to conserve kwh.
- Room 208, you have a package at the front desk.
- The Office will be closing at 10pm tonight.
- Owner of blue schwinn, please move your bike
- Watch out for ice today! We've salted the sidewalks, but it's still dangerous.

### Monthly Building Energy Usage



### Top Energy Savers



Image courtesy of REACH Community Development




# Education

- Building Owner
  - More upfront preparation/coordination required
  - Property management & maintenance staff
  - Owner's training at turnover
  - Internal bucket meetings

- Building Tenants

- Lease up
- Move in
- Ongoing

Tilt & Turn Windows or Doors





# Benefits to Residents

- Utility savings estimated at \$30-40/month
- Improved acoustics – can't hear the MAX train...
- IEQ – continuous fresh air
- High degree of thermal comfort



Photo Credit: Casey Braunger

# Resident Satisfaction

“Every day I find a new reason to love it. It’s cool, it’s quiet, and I don’t even hear the train. During the heat wave, my girlfriend came over to sleep because it was so cool. Yay for German engineering!”


Georgye Hamlin quoted in POLITICO





# Actual Performance


## Orchards Phase I Energy Use: Measured vs Modeled (PHPP)



Graph courtesy of REACH Community Development / Housing Development Center


# Actual Performance

- Apartments energy use lower than modeled
- Common area electricity use much higher than modeled
  - Causes have been investigated and troubleshooting is underway...
  - Fan at 3<sup>rd</sup> floor storage room that should be on timer is running continuously
  - Elevator usage higher than anticipated
  - Thermostats at freeze protection heaters in stairwells had been set at 70 degrees, have now been set to 45 degrees
  - DAS system added late during construction was not in original model (increasing site EUI slightly: approx. 0.2 kBtu/sf/yr)





# Actual Performance




Graph courtesy of PAE Consulting Engineers

# Enclosure Monitoring

- Monitoring performance of exterior wall assembly
- Study designed by RDH Building Science Laboratories
- Funded by ROXUL
- Will collect data for 2 years at least









**Orange** Treated Floor Area  
**Blue** Tempered Area

# Monitoring Locations





N I



RH



# Enclosure Monitoring – Interior Temp




Image used with permission from ROXUL Inc. and RDH Building Science Inc.



# Enclosure Monitoring – Interior RH




Image used with permission from ROXUL Inc. and RDH Building Science Inc.

# Enclosure Monitoring – Sheathing MC





Image used with permission from ROXUL Inc. and RDH Building Science Inc.



# Enclosure Monitoring – Sheathing RH



*Image used with permission from ROXUL Inc. and RDH Building Science Inc.*

# Enclosure Monitoring – Sheathing RH

SOUTH




Image used with permission from ROXUL Inc. and RDH Building Science Inc.



# Lessons Learned

- Owner vision - and commitment - is pivotal

# Lessons Learned

- Owner vision - and commitment - is pivotal
- It takes a team...working collaboratively, with everyone pulling in the same direction





Anchors at Orenco

REAC  
PH

# Lessons Learned

- Owner vision - and commitment - is pivotal
- It takes a team...working collaboratively, with everyone pulling in the same direction
- Early team integration pays off



# Lessons Learned

- Owner vision - and commitment - is pivotal
- It takes a team...working collaboratively, with everyone pulling in the same direction
- Early team integration pays off
- Proactive coordination and QC is essential

# Lessons Learned

- Owner vision - and commitment - is pivotal
- It takes a team...working collaboratively, with everyone pulling in the same direction
- Early team integration pays off
- Proactive coordination and QC is essential
- Keep it simple



**Cost?**

# Soft Costs - Premium

Incremental Soft Costs		
Design	Amount	Scope
Architecture	37,260	Additional coordination/research
Mechanical	19,600	PAE - Full Design for mechanical system
Energy Modeling	24,000	PAE - Energy Modeling & Incentives
PH consultant	38,720	Green Hammer
Certification	8,000	PHIUS
	21,000	Earth Advantage PHIUS on site review
<b>Total soft costs</b>	<b>\$ 148,580</b>	

Analysis courtesy of Housing Development Center

The Orchards at Oremco - Phase I  
 Passive House Energy Analysis Summary  
 Euroline Scenario (50% CD Set)  
 12/24/2013

Holiday Edition!



RESULTS		Total Source Energy EUI	
Open Planning EUI	6.24 kWh/m <sup>2</sup>	Passive House Standard	3.75 kWh/m <sup>2</sup>
Passive House Standard	4.75 kWh/m <sup>2</sup>	Percent of Limit	89%

ASPECTS		RESULTS	
Walls	100% RSI-1.00	Roofing Systems	100% RSI-1.00
Windows	U=0.80, g=0.75	Glazing Systems	U=0.80, g=0.75
Doors	U=0.30	MECH Systems	100% RSI-1.00
Roofing	100% RSI-1.00	Lighting	100% RSI-1.00
MECH	100% RSI-1.00	Control Systems	100% RSI-1.00
Lighting	100% RSI-1.00	Control Systems	100% RSI-1.00
Control Systems	100% RSI-1.00	Control Systems	100% RSI-1.00

**NOTES**

Floor area and window area inputs based on 100% DD drawings received (01/21/13) with following clarifications:  
 - where adjoining windows are not milled together, the gap between must remain same over installation as the mill condition, all doors and 2' of window

1. **Envelope Configuration:** Laundry room, elevator enclosures, and mail storage enclosures are outside the Passive House envelope. No extra heating is supplied to these spaces. Specified wall insulation, air-tightness, floor, doors and windows must separate these spaces from the building proper. Access to mechanical rooms is required to be from outside. All roof heating are assumed to occur at cold air gap areas, outside the thermal envelope.
2. **Lighting, equipment plug loads and hot water energy:** based upon Euroline details shown listed in the table for PHI compliance. Actual loads are anticipated to be higher, which increases the risk of increased discomfort due to over-heating. Strategies to encourage occupant behavior toward energy efficiency are highly encouraged. In the lobby (ballroom) reporting each unit's real-time energy usage target with reports will be how to decrease energy usage such as reducing thermal loads and night-time ventilation.
3. The attached **thermal bridge analysis** shows typical cold bridging occurred at exterior structural connections. Insulation blocking (not continuous) occurred at decks, ceilings, unconditioned wall junctions, etc. The brick masonry in the slab perimeter detail is over one inch and has been accounted for as a thermal bridge.





# Hard Costs - Premium

Description	Amount
Additional construction duration	\$ 31,500
Additional supervision/QC	\$ 25,000
Overexcavation for underslab insulation	\$ 10,000
2x10 stud wall - additional material cost	\$ 60,000
Fero clips/brick detailing	\$ 20,000
Detailing/material for separating interior PH spaces	\$ 10,000
Siding return detail for overinsulation	\$ 20,000
Additional flashing details	\$ 20,000
Roofing insulation	\$ 50,000
Wall insulation	\$ 53,907
Slab on grade insulation	\$ 55,711
Windows and Deck Doors	\$ 176,217
Commercial doors, including interior PH doors	\$ 38,443
HVAC	\$ -
Infiltration costs	\$ 83,886
Hot water heater	\$ 2,000
Low flow fixtures	\$ 3,480
Temp maintenance system	\$ 15,000
Lighting	\$ -
Appliances	\$ 6,256
Energy monitoring system	\$ 87,000
Elevator	\$ -
Siding/rain screen	\$ 20,000
Blocking, Hold offs, SAM	\$ 25,000
Air Testing	\$ 10,000
Other misc. costs	\$ 50,000
	Subtotal \$ 873,400
	Markup \$ 37,120
	Total hard costs \$ 910,520

Analysis courtesy of Housing Development Center



# Cost Premium & Financing

## Uses

Incremental Soft Costs	\$ 148,580	
Incremental Hard Costs	\$ 910,520	
Total incremental Cost	\$ 1,059,100	
Premium over "typical Orenco"		11.0%

## Sources

REACH Equity	\$ 300,000	
Meyer Memorial Trust grant	\$ 500,000	
Neighborworks grant	\$ 260,000	
OHCS Weatherization	\$ 100,000	
Energy Trust of Oregon	\$ 65,000	
Enterprise charrette grant	\$ 4,000	
<b>Total additional Sources</b>	<b>\$ 1,229,000</b>	

Analysis courtesy of Housing Development Center



**Would We Do It Again?**



# Orchards at Orenco Phase II



# Orchards Phase I & II


## Phase I (PHIUS+ Certified)

- Innovate to meet REACH strategic goal of building Passive House
- REACH brought significant private investment for this innovation

## Phase II (Passive House Inspired)


- Meet OHCS cost containment limits
- Additional private resources not available
- Take lessons learned & best practices from Phase I

# Design Response to Cost Containment



## Phase II (original design)

- L-shaped building with 46 parking stalls
- 57 units in 57,750 SF
- Shallow units to increase daylight
- Community room, office



## Phase II (after design revisions)

- Bar building with 77 parking stalls
- 58 units in 49,900 SF
- Deeper, narrower units
- Reduced number of balconies
- Reduced amenity space
- Reduced open space





# Orchards Phase I & II

## Phase I

(PHIUS+ Certified)

- Envelope
  - Fully insulated slab & footings
  - 2x10 walls with 1 ½” exterior insulation
  - Triple-glazed windows
  - Low-slope roof with R-81 insulation
- Whole building ERV with heat pump
- Spaces outside conditioned envelope = very expensive doors & detailing
- Ultra airtight: 0.13 ACH50
- Extended sequencing / duration

## Phase II

(pursuing PHIUS+ Certification)

- Envelope
  - Insulated slab. No insulation under footings
  - 2x8 walls with 1” exterior insulation
  - Triple-glazed windows
  - Steep-slope roof with R-60 insulation
  - Vented attic
- Reduced vertical envelope area
  - 35,000 SF → 27,700 SF
- Same HVAC as Phase I, but with better zoning due to orientation of building
- All spaces inside conditioned envelope
- Airtight??????






Image courtesy of Ankrom Moisan Architects

# Building Section



Tyvek

HYDRO MOB



















Sheathing  
GP  
Glass



GP  
Glass  
Sheathing

GP  
Glass  
Sheathing

39 44 50





















94.6



73.1

 FLIR



94.6



**Final Airtightness Test Results: 0.42 ACH<sub>50</sub> (taped)**

**0.59 ACH<sub>50</sub> (untaped)**

73.1  
102



# Orchards Phase I & II

## Phase I

(PHIUS+ Certified)

- TDC of \$14.5M
- \$255K/unit
- Construction cost: \$9,093,040
- \$158/SF
- \$159,527/unit
- Energy performance:
  - 5 energy models
  - 31-71% better than code
  - Actual data available now

## Phase II

(pursuing PHIUS+ Certification)

- TDC of \$13.6M
- \$234K/unit
- Construction cost: \$8,531,624
- \$173/SF
- \$147,097/unit
- Energy performance:
  - 3 energy models
  - 29-67% better than code
  - Actual data available in 2017



# More Information & Insights

- REACH Community Development:
  - [http://reachcdc.org/main/docs/housing\\_development/Orchards\\_PH\\_Case\\_Study.pdf](http://reachcdc.org/main/docs/housing_development/Orchards_PH_Case_Study.pdf)
  - [http://reachcdc.org/main/docs/housing\\_development/Orchards\\_at\\_Orengo\\_I\\_Development\\_Profile\\_update\\_Aug\\_2015.pdf](http://reachcdc.org/main/docs/housing_development/Orchards_at_Orengo_I_Development_Profile_update_Aug_2015.pdf)
- Housing Development Center:
  - <http://www.housingdevelopmentcenter.org/our-work/buildings/orchards-at-orengo/>
- Ankrom Moisan Architects:
  - <https://www.youtube.com/watch?v=ewJUCWI6dqM>
- PHIUS Case Study:
  - <http://www.phius.org/phius-certification-for-buildings-and-products/case-studies/orchards-at-orengo-phase-i>
- BEST 4 Conference Paper:
  - <http://walshconstructionco.com/2015/04/walsh-presents-at-best-4-building-enclosure-science-and-technology-conference/>
- Guest Blog on Green Building Advisor:
  - <http://www.greenbuildingadvisor.com/blogs/dept/guest-blogs/largest-passivhaus-building-us>

# Q & A